



## ADDENDUM #1

### Sodom Dam & Shearer Dam Removals (June 2, 2011)

---

The following clarifications, changes, additions, and/or deletions are hereby made a part of the Contract Documents for the Sodom Dam and Shearer Dam Projects as fully and completely as if the same were fully set forth herein and must be acknowledged in the Proposal.

**CLARIFICATION:** Section 2200 (Earthwork), 3.01.E states Contractor is responsible for additional fill if areas settle below required grades for one year. This primarily covers areas where fill has been imported and settlement occurred as a result of Contractor deficiencies in compaction effort. This only applies to areas of imported fill.

**CHANGE:** Section 5000 part 2.2 and 3.5, "rebar anchors" shall be replaced with "all thread rod" to be consistent with Drawing 4.0.

**CLARIFICATION:** Access will be allowed on the river left top of bank, however, disturbances must be minimized as this is an area of known archeological sites. Access to the west side of Sodom Ditch will have to be from the construction staging area and will not be allowed from Linn-West Road.

**CLARIFICATION:** Boulders for ballasting large wood shall be angular and all wood will be provided by the Contracting Agency.

**CHANGE:** Section 5007 part 2.1 shall specify Dekowe 900 coir mat to be consistent with Drawings 4.9 and 4.10.

**CLARIFICATION:** Water from the Calapooia and Sodom Ditch can be used for irrigation purposes. Long-term irrigation after the project will be handled by the Calapooia Watershed Council.

**CLARIFICATION:** Cut willow stakes will be the Contractor's responsibility from local willows near the project site. Rooted willows will be provided by the Calapooia Watershed Council. Most of the rooted willows will be placed in the vegetated soil lifts. Remaining rootwed willows to be planted as part of the Channel Margin Treatment detail will require holes be dug for placement. It is estimated that 3,000 - 4,000 rooted willows will be provided to the Contractor in gallon sized pots.

**CLARIFICATION:** Areas will be available for temporary stockpiling of excavated materials and will be determined in consultation with the Contractor and Project Inspector.